

SPECIFICATIONS

Test Point

A Test Point shall be installed at the inlet and outlet of each pump, balancing valve and heat exchange equipment like Chiller, Condenser, Cooling Tower, Water Cooling Coil, Boiler. Test Points shall also be provided at different locations in the water pipe line to facilitate pressure measurement.

Test Point shall be of brass construction, 1/4" BSP with NEOPRENE sealing bushes and shall be provided with screwed cover.